

OFFICE OF THE SUPERINTENDENT, HILL STATIONS IN MYSORE,
LAL-BAGH, BANGALORE.

Dated 12th December 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Superintendent, Hill Stations, Lal-Bagh, Bangalore, up to 3 p.m. on 23rd December 1932, for repairs to be done to Bungalows in the Nandi Hill Station up to the end of June 1933. Approximate quantities of work to be done are given below, though these quantities are not guaranteed.

2. Tenders should be submitted on printed forms (which may be obtained from the office of the undersigned) showing the rates at which different items specified will be executed.

3. Each tender must be accompanied by a deposit of rupees one hundred in cash as earnest money and it should be superscribed "Tender for building repairs to, in Nandi Hill Station," in default of which, tenders will be rejected.

4. The final acceptance of any tender will rest with the Superintendent, Hill Stations, who does not bind himself to accept the lowest or any tender or to assign any reason whatsoever for the rejection of any tender.

5. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be cancelled and his earnest money will be forfeited to Government.

6. The successful competitor whose tender is accepted will be informed in due course. No enquiries regarding the acceptance or rejection of tender will receive any reply.

7. The earnest money on rejected tenders will be returned.

8. Rate should be quoted for each item of work.

9. Percentage rates either below the estimated amount or the lowest tender will not be accepted.

10. In case of non-tendered item the departmental rates should be accepted by the Contractor.

11. No claims for enhanced rates should be preferred at any time during the course of the period.

12. In all matters of dispute regarding quality of work or rates, etc., the decision of the Superintendent, Hill Station is final.

13. Abstract of the approximate quantities of repair works to be done to Government Bungalows in the Nandi Hill Station.

No.	Items of works	Unit	Quantity	Rate
1	Two coats whitewash after repairing cracks, holes, etc., in chunam.	Sqr.	650	
2	Two coats distemper wash after repairing cracks, holes, etc. in chunam.	"	100	
3	Two coats cement wash after repairing the cracks, holes, etc., in chunam.	"	300	
4	Two coats colour wash after repairing the holes and cracks, etc., in chunam.	"	100	
5	Two coats of Silicate paint after cleaning the old paint.	"	100	
6	Renewing glass panes $\frac{1}{8}$ inch thick	Sq. ft.	50	
7	Iron Hooks 3" ...	Each	50	
8	Do 6" ...	"	50	
9	Do 9" ...	"	50	
10	Do 1" ...	"	50	
11	Tower bolts of sizes ...	Each inch	500	
12	Chunam pointing	Sqr.	50	
13	Chunam plastering	"	50	
14	Teakwood wrought and put up	C.ft.	50	
15	Do windows with iron bars, etc.	S.ft.	50	
16	Do doors with panel shutters complete of $\frac{1}{2}$ "	"	100	
17	Burnt brick in mud	C.ft.	200	
18	Burnt brick in chunam	"	200	
	Stone work in mud	"	200	
	Stone work in chunam	"	200	
19	Stone slabs including two line dressing and fixing in chunam and cement pointing.	Sq.ft.	200	
20	Flooring with 1st Class Mangalore clay tiles on 3" concrete and cement painting complete.	"	20	
21	Gravelling roads and paths...	Sq.yds.	2,000	
22	Cleaning side drains	R. "	5,000	

H. C. JAVARAYA,
Superintendent.